REQUEST TO COUNTY ROAD DEPARTMENT FOR REIMBURSEMENT OF WORK

To The County Engineer:

Pursuant to terms of an agreement between the county and the **City of Okanongan** adopted and approved on **June 28, 2016** the undersigned hereby requests the county to perform the work listed below at a time and in a manner convenient to the county. The undersigned further requests that the work be completed no later than **August 31** and hereby guarantees reimbursement to the county for all work done up to a maximum of **$13,000**

.

Chip Seal of the city's sections of Okanogan Landfill Road and Okanogan Airport Road.

All terms of said agreement shall apply with the following exceptions:
(**list exceptions if any**)

DATE____________________ SIGNATURE________________________

(Agency Representative) TITLE_____________________________

****

To The Board of County Commissioners: DATE_________________

I have examined the above request and make the following recommendations:

☐ Recommend approving.
☐ Recommend not approving:

SIGNATURE________________________ (County Engineer)

****

Action of the Board of County Commissioners: DATE_________________

☐ The Engineer's recommendation is hereby approved.
☐ The Engineer's recommendation is not approved or modified as follows:

BOARD OF COUNTY COMMISSIONERS
OKANOGAN, WASHINGTON

ATTEST:

____
Andy Hover, Chairman

____
Jon Neal, Member

____
Nick Timm, Member

____
Stacy Nicole McClellan,
Deputy Clerk of the Board

CRAB Form 102

Okanogan(2026)

	Road Name	Length ft	Mileage	Width	Sq. yrds	App. Rate	Gallons	Tons Needed	Rock Yd.
	Okanogan Airport	500	0.095	22	1222	0.42	513	2	16
	Land Fill Road	1200	0.227	22	2933	0.42	1232	5	38
	Total		**0.322**		**4155.556**		**1,745**	**7**	**54**

	Rock	$	**737.40**
	liquid asphalt	$	**5,340.22**
	labor	$	**1,205.11**
	equipment cost	$	**1,953.11**
	Subtotal	$	**9,235.84**
Admin	10%	$	923.58
	Total w/ Adm.	***$***	***10,159.43***

Rock-Baily Pit (Nespelem)	$ 9.54
Rock-Central Pit (Okangon)	$ 13.65
Rock-Miller Pit (Twisp-Brewster)	$ 9.57
*liquid asphalt	$ 719.34
**labor	$ 0.29
*equipment cost	$ 0.47
Admin	10%
*Just an estimate on cost increases	
**Based on average w/wage increases	